

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 15- TWP. 30S RGE. 14W E/W
Location as in quarters or footage from lines:
C of SW/4

Locate Well
correctly on above
Section Platt.

Lease Owner E.G. Hall
Lease Name Staate #1-15 Well No. _____
Office Address 6427 East Kellogg Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 7/8/81
Plugging completed 7/13/81
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation _____ Depth to top _____ bottom T.D. 4748'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	365'	None
				4 1/2"	4744'	3515'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Moved in on location, made bottom hole plug back with sand to 4550' and ran 4 sacks
cement. Made shots at 3630', and 3500'. Pulled total of 81 joints. Squeezed hole
with 15 sacks gel, 6 sacks hulls and 10 sacks gel. Released plug and displaced
with 125 sacks 50/50 pos 4% gel and 3% cc. Plugging complete.

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1981

7-22-81
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 81

My Commission expires:



Joan Kelso
Notary Public.