

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-007-22344-00-91

LEASE NAME JOHNSON

WELL NUMBER 1-11

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 11 TWP. 30S RGE. 14 KRXR (W)

COUNTY BARBER

Date Well Completed \_\_\_\_\_

Plugging Commenced 1-18-93

Plugging Completed 1-21-93

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR F G HOLL CO.

ADDRESS P O BOX 180167 6427 EAST KELLOGG WICHITA, KS.

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 67276-0167 5056

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on JANUARY 20, 1993 (TOP HOLE PLUG) (date)

by STEVE MIDDLETON (DODGE CITY DISTRICT) (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4154

PERFS: 4481-4500; 4454-4460; 4032-4040; 4167-4169; 4187-4189; 4200-4203; 3812-3815;  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	218	13 3/8	218	0
		0	4688	4 1/2	4688	3013 ft. 71 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
1-18-93: DUMPED SEVEN BBLs. OF SAND, SANDED BACK TO 3635 FT. 1-19-93: DUMPED FOUR SX. CEMENT  
RIGGED TO PULL CASING, TOP OF CEMENT: 3585 FT. 1-20-93: SHOT 4 1/2 CASING OFF AT 3013 FT, PULLED 71  
JTS. OF CASING 1-21-93: HALLIBURTON PUMPED 400# HULLS, 20 SX. GEL, 225 SX. CEMENT. 60-40 POZ.  
6% GEL.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. STATE CORPORATION COMMISSION

Address P O BOX 847 PRATT, KANSAS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F G HOLL CO.


STATE OF KANSAS COUNTY OF PRATT, ss.

RECEIVED  
 STATE CORPORATION COMMISSION  
 1-27-93  
 JAN 27 1993  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

JUDY BERRY (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) C/O PRATT WELL SERVICE, INC.



Subscribed and sworn to before me this 25th day of January, 1993

Dorothy M. Ferguson  
 Notary Public

My Commission Expires: Feb. 6, 1993

15-007-22344-00-01 ✓

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- JOHNSON #1-11  
Located: NW NW NW, Section 11-30S-14W, Barber County,  
Kansas

OWNER: F. G. Holl Company  
DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 24, 1990  
COMPLETED: December 5, 1990

TOTAL DEPTH: 4690'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 220 Surface Soil and Red Bed	Ran 5 joints 13 3/4", 48# casing.
220 - 690 Shale - Red Beds	205.84' pipe set at 218 K.B.
690 - 920 Shale and Lime	Cemented with 225 sacks 60/40 Pozmix, 2% gel, 3% cc. Plug down at 3:00 PM, 11-24-90, by Howco.
920 - 940 Anhydrite	
940 - 4690 Lime and Shale	Ran 113 joints 4 1/2" casing (308.92' used). 4691.93' pipe set at 4688' K.B. Cemented with 20 bbls. salt flush, 500 gallons super flush, 100 sacks Lite, 125 sacks F. G. Holl mix. Plug down at 3:00 AM, 12-5-90, by Howco.

**RECEIVED**  
KANSAS CORPORATION COMMISSION

OCT 20 1992  
10-20-92  
CONSERVATION DIVISION  
WICHITA, KS

Deviation Surveys: 3/4° at 2965'  
1 1/4° at 4690'