

15-007-30284-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 26 Twp. 31S Rge. 14W (Ex (W)

Location as "NE/CNW&SW" or footage from lines NE SW NE
Lease Owner Leben Drilling, Inc.
Lease Name Lake Well No. 1
Office Address Box 486, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-6-67 19__
Application for plugging filed 1-6-67 19__
Application for plugging approved 1-6-67 19__
Plugging commenced 1-6-67 19__
Plugging completed 1-6-67 19__
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4780 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	882'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 400' - 1/2 sk. hulls - plug 25 sks. cement
Mud to 40' - 1/2 sk. hulls - plug 10 sks. cement
put 2 sks. in rathole

RECORDED
INDEXED
JAN 13 1967
1-13-67
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of January, 1967

Glaude Nichols
Notary Public.

My commission expires April 1, 1967

DRILLER'S LOG

COMPANY: Leben Drilling, Inc. etal
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: LAKE #1
 LOCATION: NE SW NE SEC. 26-31S-14W
 BARBER COUNTY, KANSAS
 COMMENCED: 12-15-66
 COMPLETED: 1-6-67

0	100	Redbed
100	883	Red Shale
883	1850	Shale
1850	2230	Lime
2230	2350	Lime, Shale
2350	2505	Lime
2505	3125	Lime, Shale
3125	3330	Lime
3330	3835	Lime, Shale
3835	3875	Shale
3875	4470	Lime
4470	4535	Lime, Shale
4535	4575	Lime
4575	4621	Lime, Chert
4621	4674	Lime
4674	4730	Lime, Shale
4730	4780	Lime
	<u>4780</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 13 1967
 1-13-67
 CONSERVATION DIVISION
 Wichita, Kansas

8 5/8" new surface casing Set @ 882' with Basket Set @ 721'; cemented bottom with 150 sacks Common, 2% cc. Plug down at 11:30 p.m. Cemented top through 1" pipe with 15 sacks cement. Waited on cement 2 hours then cemented through 1" pipe with approximately 125 sacks cement, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Lake #1 Well, located NE SW NE of Section 26, Township 31 South, Range 14 West, Barber County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, this 10th day of January, 1967.

Ulanda Nichols

Ulanda Nichols

My Commission Expires
 April 1, 1967