

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barber SEC. 5 TWP. 30S RGE. 14W E/W  
Location as in quarters or footage from lines:  
NWNENE


Lease Owner Anatole Oil Corporation  
Lease Name Lenkner Well No. 1  
Office Address 609 One Tandy Center, Ft. Worth, Texas 76102  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 12-23-81  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 12-23-81  
Plugging completed 12-23-81  
Reason for abandonment of well or producing formation \_\_\_\_\_  
Dry Hole

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice V. Leslie

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4730'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
surface				8-5/8	466'	none

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

- 60sks @ 720'
- 40sks @ 450'
- 10sks @ 40'
- 10sks Rathole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

STATE OF Texas COUNTY OF Tarrant, ss.

Robert D. Baker (employee of ~~owner~~) or (~~owner~~ or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Robert D. Baker  
Same as above  
(Address)

SUBSCRIBED AND SWORN TO before me this 4 day of Feb, 19 82

Chris Pasichy  
Notary Public.

My Commission expires: MY COMMISSION EXPIRES 12-29-85

GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

Lenkner #1  
 SW-NE-NE Sec 5-30S-14W  
 Barber County Kansas

Commenced: 12-15-81

Completed: 12-23-81

OPERATOR: ANATOLE OIL CORPORATION

Depth		Formation	Remarks
From	To		
0	150	Clay-Sand	Ran 11 jts of 20# 8 5/8" csg set @ 466' Cemented w/375 sks Common 2% Gel - 3% CC PD @ 5:30 p.m. 12-15-81
150	600	Redbed	
500	2190	Shale	
2190	2700	Shale-Lime	
2700	2950	Shale	
2950	3345	Lime-Shale	
3345	3585	Shale-Lime	
3585	3775	Lime	
3775	4145	Lime-Shale	
4145	4730	Lime	
	4730 - TD		DRY & ABANDONED

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

*James S. Sutton II*  
 JAMES S. SUTTON II

Subscribed and sworn to before me this 29th day of December, 1981.

*Elizabeth J. Edwards*  
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

113110