


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 18 Twp 20S Rge 22W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner Shell Oil Company
Lease Name Sekavic Well No. 1-18
Office Address 1200 1st Nat'l Bldg., Okla. City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-28-66 19__
Application for plugging filed 4-28-66 19__
Application for plugging approved 4-28-66 19__
Plugging commenced 4-28-66 19__
Plugging completed 4-28-66 19__
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4365 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	266'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded to 540', set plug w/25 sks. cement
Mudded to 260', set plug w/20 sks. cement
Mudded to 40', set plug w/10 sks. cement

RECEIVED
STATE CORPORATION COMMISSION

MAY 2 - 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April, 19 66

Ulanda D. [Signature]
Notary Public.

My commission expires April 1, 1967

DRILLER'S LOG

15-135-30190-0000

COMPANY: Shell Oil Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: SEKAVIC #1-18
 LOCATION: C SW NE Sec. 18-20S-22W
 NESS COUNTY, KANSAS
 COMMENCED: 4-16-66
 COMPLETED: 4-28-66

0	268	Shale
268	787	Shale, Redbed
787	805	Hard Sand
805	1050	Sand
1050	1410	Shale
1410	1423	Red Rock Shale
1423	1490	Anhydrite
1490	1835	Shale, Shells
1835	2200	Shale
2200	2380	Shale, Lime
2380	2474	Shale, Broken Lime
2474	3793	Lime, Shale
3793	4365	Lime
	<u>4365</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 2 - 1966
 CONSERVATION DIVISION
 Topeka, Kansas

Set 8 5/8" new 20# surface casing @ 266' with 185 sacks Common
 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is
 a true and correct copy of the log of the Sekavic #1-18 well, located
 C SW NE of Section 18, Township 20 South, Range 22 West, Ness County,
 Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in
 and for Barton County, Kansas, this 30th day of April, 1966.

Ulanda Nichols

Ulanda Nichols

My commission expires: April 1, 1967