

API NUMBER N/A 15-135-30188-0000
LEASE NAME Stairrett "A"
WELL NUMBER 1
1980 Ft. from S Section Line
660 Ft. from E Section Line
SEC. 18 TWP. 20S RGE. 22W (E) or (W)
COUNTY Ness

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Joe Gerstner Oil
ADDRESS 302 E. Sycamore, Ness City, Ks. 67560
PHONE#(913) 798-2893 OPERATORS LICENSE NO. 9615

Date Well Completed 3/12/66
Plugging Commenced 6/18/97
Plugging Completed 6/18/97

Character of Well casing leak
(Oil, Gas, D&A, SWD, Input, Water Supply Well)
The plugging proposal was approved on May 22, 1997 (date)
by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? No
Producing Formation Mississippian Depth to Top 4308 Bottom 4335 T.D. 4335

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			CASING RECORD			
Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8 5/8"	230'	None
	Production			5 1/2"	4325'	None

7-16-97
7-16-97
KANSAS
FILED
JUL 16 1997
JUL 16 1997

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet, each set.
Circulate hole 1st plug 4130'. Mix 25 sks 60/40 Poz 6% gel 75# hulls displaced to balance,
Pulled tubing to 750', mixed 80 sks 60/40 poz 6% gel and 225# hulls Cement circulated top
out with 20 sks. Pump no sks down annulus full. Pressure to 500# with 1/2 bbl Held.


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hembree Well Service License No. 32066
Address P. O. Box 458, Ness City, Ks. 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Joe Gerstner Oil
STATE OF Kansas COUNTY OF Ness, ss.

Joe Gerstner (Employee or Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Joe Gerstner
(Address) _____



SUBSCRIBED AND SWORN TO before me this 8th day of July, 19 97
Karen Stoecklein
Notary Public
My Commission Expires: 4-24-2000