


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ness County, Sec. 18 Twp. 20S Rge. (E) 22(W)
Location as "NE/CNWxSWx" or footage from lines 150' SW of C NE NW
Lease Owner Pickrell Drilling Company
Lease Name Gross "A" Well No. 2
Office Address 705 4th National Bank Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 21, 19 66
Application for plugging filed April 21, 19 66
Application for plugging approved April 21, 19 66
Plugging commenced April 21, 19 66
Plugging completed April 21, 19 66
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4410 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	257'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 540', set plug, cemented with 25 sacks cement. Heavy mud to 250', set plug, cemented with 20 sacks cement. Heavy mud to 45 feet, set plug, cemented with 10 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1966
4-27-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.

C. W. Sebitts (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C. W. Sebitts*
C. W. Sebitts,
705 4th National Bank Building, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 25th day of April, 19 66



Maxine Blackman
Maxine Blackman, Notary Public.

My commission expires June 21, 1966

ROTARY DRILLING LOG

15-135-30186-0000

COMPANY: PICKRELL DRILLING COMPANY
705 Fourth Natl Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 4-11-66

Rotary Drilling Completed 4-20-66

LOCATION: Gross "A" No. 2, 150' SW of C NE NW Section 18-20S-22W, Ness County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (11 jts) 8 5/8" surface casing set at 257', cemented with 165 sacks cement. Circulated. Completed 5:00 P.M. April 11, 1966. No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

90	Post Rock	<u>C. F. S.</u>
160	Shale & Shells	4342
258	Shale & Sand Streaks	4350
605	Shale	4355
808	Red Beds	4363
821	Blaine	4369
1440	Shale, Shells & Red Beds	4374
1481	Anhydrite	4410
2165	Shale & Shells	
2435	Lime & Shale	
2685	Lime	<u>Slope Tests</u>
3238	Shale & Lime	2500
3430	Shale	3000
4333	Lime & Shale	3600
4342	Chert - Shale	4100
4410	Mississippian - RTD	

<u>S. L. M.</u>
3749
4083
3227

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1966
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 25th day of April, 19 66, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public