

15135-20599-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec. 15 Twp. 20S Rge. (E) 22 (W)

Location as "NE/CNW&SW&" or footage from lines NE SE
Lease Owner Thunderbird Drilling, Inc.
Lease Name Hunt Well No. 1
Office Address 4328 East Kellogg, P. O. Box 18407, Wichita, Kansas 67218
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 19 19 72
Application for plugging filed April 19 19 72
Application for plugging approved April 19 19 72
Plugging commenced April 19 19 72
Plugging completed April 19 19 72
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4412 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	337.36'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Plugged hole as follows: Plugged at 540' with 50 sacks of regular cement; plugged at 300' with 25 sacks of regular cement; plugged at 40' with 10 sacks of regular cement. Plug down at 9:25 A. M. April 19, 1972.

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1972
4-27-72
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530


STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of April, 19 72

My commission expires December 14, 1973

Elaine H. Taylor
Elaine H. Taylor Notary Public.



DRILLERS LOG

15-135-20599-0000

#1 Hunt

CASING RECORD:
331.36' of used 8-5/8"
surface casing.

COMPANY: Thunderbird Drilling, Inc.
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: NE SE
Section 15-20S-22W
Ness County, Kansas

TOTAL DEPTH:
4412'

COMMENCED: April 10, 1972
COMPLETED: April 19, 1972

ELEVATION: 2237' GL

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Post Rock, Shale & Sand	0	365	Ran 331.36' of used 8-5/8" surface casing; set and cemented at 337.36' with 190 sacks of common cement, 2% gel and 3% C. C. Plug down at 11:30 P. M. April 10, 1972.
Shale	365	465	
Shale, Red Bed with Sand Streaks	465	1379	
Red Bed & Shale	1379	1475	
#2 Anhydrite	1475	1511	
Red Bed, Blue Shale & Shells	1511	1820	
Shale w/Lime Streaks	1820	2430	
Lime & Shale	2430	3217	
Lime	3217	3627	
Shale & Lime	3627	3786	
Lime	3786	4323	
Lime, Shale & Chert	4323	4362	
Lime	4362	4407	
Sand & Lime	4407	4412	

ROTARY TOTAL DEPTH 4412'

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1972
CONSERVATION DIVISION
Wichita, Kansas

D. & A.

Plugged hole as follows: Plugged at 540' with 50 sacks of regular cement; plugged at 300' with 25 sacks of regular cement; plugged at 40' with 10 sacks of regular cement. Plug down at 9:25 A. M. April 19, 1972.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 24th day of April, 1972.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1973