

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-13530144-0001
API NUMBER Drill date 10-8-65

LEASE NAME Gross

WELL NUMBER 1-18

4620' Ft. from S Section Line

4620' Ft. from E Section Line

SEC. 18 TWP. 20 RGE. 22 (E) or (W)

COUNTY Ness

Date Well Completed _____

Plugging Commenced 1-30-90

Plugging Completed 1-30-90

LEASE OPERATOR Alpine Petroleum Inc.

ADDRESS P.O. Box 66 El Dorado, KS 67042

PHONE#(316) 685-1722 OPERATORS LICENSE NO. 3762

Character of Well _____

(Oil) Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-26-90 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Mississippi Depth to Top 4320' Bottom 4350' T.D. 4375'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION
2-1-90

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	256'	none
				4 1/2"	4357'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Pumped 75 sx. econolight with 300# hulls down 4 1/2", displaced cement with water to 1000', perforated 4 1/2" @ 800', pumped 100 sx. 60/40 6% down 4 1/2" displacing 50 sx. through perfs. 100 sx. 60/40 6% down 4 1/2" X 8 5/8" annulus

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Plains, Inc. License No. 4072

Address Box 346, Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Alpine Petroleum Inc.

STATE OF Kansas COUNTY OF Ness, ss.

Clint Base

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Clint Base

(Address) Box 346, Ness City, KS 67560

CONNIE J. BASE

NOTARY PUBLIC
STATE OF KANSAS

My Appt. Exp. 5-5-90

My Commission Expires: 5-5-90

Notary Public