



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

CP2

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1962
7-18-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date 7-13-1962, 1961, authorized the following plugging operation:

Operator's full Name: Time Petroleum Co.

Complete Address: 815 Union National, Wichita, Kansas

Lease Name: Mills Well No. 1

Location: NW1/4NW1/4 Sec. 31 Twp. 31 Rge. 14 (E)(W)X

County: Barber Total Depth: 4843'

Oil Well Gas Well Input Well SWD Well

D & A Other well as hereafter indicated:

Operator was instructed to plug well as follows:

268' of 8 5/8" surface pipe. Hole filled with heavy drilling mud to 240'. 1/2 sack hulls and first cementing plug with 20 sacks cement through drill pipe. Filled to 40' with heavy drilling mud. 1/2 sack hulls and second cementing plug and 10 sacks cement to bottom of cellar. Rathole bridged and 2 sacks cement.

Very truly yours,

Herman Justus

