

State of Kansas



15-135-70568-6800

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cameran of H - 30 Drlg. has this

date requested permission to plug the following described well:

Mr. Cameran guarantees payment of the plugging fee.

Operator's full Name: Kathol Petroleum, Inc.

Complete Address: 900 Sutton Place Wichita, Ks.

Lease Name: Foss Well No. 1

Location: C SE NW Sec. 8 Twp. 20 Rge. (E)(W) 22

County: Ness Total Depth 4440' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Cameran was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and ~~XXXX~~
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Rev. F. M. M. M.
Conservation Division Agent