

DISTRICT CONSERVATION AGENT'S REPORT

Handwritten initials 'CB' and a large stylized 'R' with a diagonal slash.

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 20-21

LOCATION NE-7165-26

SEC. 16 TWP. 31 RGE. 14-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well <sup>✓<sub>20</sub></sup> X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Skinner-10"

Operator Bishop Oil Co. Address #316 Brown Bldg. Wichita-Kans.

Field \_\_\_\_\_ County Barber

Total Depth 4385' Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 1 3/4" - 800 ft. Circulated with cement  
5/8" casing set at 435 ft. Circulated with 150 sacks cement.  
Mud to 3602 ft. True Well Plug at 3602 ft. Filled with  
shot from 3602 ft to 3583 ft. Dumped 5 sacks of cement at  
3583 ft. Plot off & pulled the 5/8" casing - Mud to 250 ft  
Set Rock Bridge & 20 sacks of cement at 250 ft. Mud to  
35 ft. Bridge & 10 sacks of cement at the surface -  
Walt Supply Co - Plugging Contractors

RECEIVED  
STATE CORPORATION COMMISSION

OCT 13 1950  
10-13-50

WICHITA, KANSAS  
District Conservation Agent C. D. Strough

Date 10-10-50

**PLUGGING**  
FILE SEC 16 TWP 31 R 14W  
BOOK PAGE 30 LINE 21