

15-135-30013-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 17 1965
2-17-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mobil Oil Co

Complete Address: Box 1070 Great Bend, Kans

Lease Name Whitman Well No. 1

Location CNE SE Sec. 12 Twp. 20 Rge. (E) (W) 22

County Ness Total Depth 4342

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: lost hole

Plugging Contractors: Hay Drg Co & Halliburton Co

Address: Hoisington, Kans License No. 118

Operation Completed: Hour 4:30PM Day 12 Month 2 Year 65

The Above well was plugged as follows:

8 5/8" 327' circulated with cement - 5 1/2" 4328' with 75 sax cement
5 1/2" collapsed at 3539' - cut off 5 1/2" at 2370' - pulled pipe -
circulated hole with heavy mud through tubing at 620', displaced 25 sax
cement through tubing at 620', heavy mud to 310', displaced 25 sax
cement through tubing at 310', heavy mud to 35', cement 35' to 0'

Cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 2/17/65

INV. NO. 695-4