

15-135-20196-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Brandt - Clark

Complete Address: 737 First Nat'l Bk. Bldg., Wichita, Kansas

Lease Name Wittman Well No. 1

Location C NE SW Sec. 12 Twp. 20 Rge. 22 (E) (W) XX

County Ness Total Depth 4402

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Leben Drlg.

Address: Wichita, Ks. License No.

Operation Completed: Hour 2P Day 30 Month 10 Year 1968

The Above well was plugged as follows:

RTD 4402 8 5/8 csg set at 533' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 50 sc cmt.
thru drill pipe. Heavy mud to 500' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Massey
Well Plugging Supervisor

DATE 11/2/68
INV. NO. 8737-U