

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -135 -21,538-0000 (of this well)

Operator's Full Name Vincent Oil Corp/.  
Complete Address 230 O. W. Garvey Bldg., Wichita, Kansas  
Lease Name Schwien "C" Well No. 1  
Location C SE SW Sec. 11 Twp. 20 Rge. (E) (W) 22  
County Ness Total Depth 4395'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Slawson Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 6:45 A Day 28 Month 11 Year 1978

The above well was plugged as follows:

RTD 4395' 8 5/8 csg set 486' cwc Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.

Heavy mud to 300' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 30 1978

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11-30-78  
INV. NO. 8643-U

Signed: Leo Messing  
Well Plugging Supervisor