

15-135-207620000

Form CP-3
Rev. 6-4-68

KANSAS

AL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name C - G Drilling Company

Complete Address 1107 Union National Bldg., Wichita, Kansas

Lease Name Stoecklein Well No. 1

Location NE NE Sec. 10 Twp. 20 Rge. (E) (W) 22

County Ness Total Depth 4450'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 12 N Day 4 Month 8 Year 1971

The above well was plugged as follows:

RTD 4450' 8 5/8 csg set at 351' cwc. Cmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 50 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 8-10-71

INV. NO. 4121-W