

15135-20568-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1972
CONSERVATION DIVISION
Wichita, Kansas
1-31-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Kathol Petroleum, Inc.
Complete Address 900 Sutton Place Wichita, Kansas
Lease Name Foss Well No. 1
Location C SE NW Sec. 8 Twp. 20 Rge. (E) (W) 22
County Ness Total Depth 4440'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor H-30 (Rotary)
Address Wichita, Kansas License No.
Operation Completed: Hour 7 A Day 28 Month 1 Year 1972

The above well was plugged as follows:

RTD 4440' 8 5/8 csg set at 261' cwc. Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Paul J. Massey
Well Plugging Supervisor

DATE 2-1-72
INV. NO. 5103-W