

40
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1964
1-6-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum Management Inc.

Complete Address: 1515 Wichita Plaza, Wichita, Kansas

Lease Name Lambert Well No. # 1

Location C S/2 SW NE Sec. 35 Twp. 30 Rge. 14 (E) (W) W

County Barber Total Depth 605

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: This was a wash down, and 605' was all the depth that could be reached, due to an obstruction in hole.

Plugging Contractor: Bowers Drilling Co.

Address: 416 Union Center Bldg., Wichita, Kansas License No.

Operation Completed: Hour 1:00PM Day 2nd Month Jan. Year 1964

The Above well was plugged as follows:

726' of 13 3/8" surface pipe, cement circulated. Hole was filled with drilling mud to 300', 1st cementing plug, bridged with 2 sacks of hulls, and cemented with 35 sacks. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1 sacks hulls, and cemented with 22 sacks to base cellar.
Rat hole bridged and cemented with 3 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1/7/64
INV. NO. 8422-44

Signed: Archie Elving
Well Plugging Supervisor