

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

R

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-007-00704-0000 (of this well)

Operator's Full Name Gear Pet., Co.

Complete Address 1325 Vickers, KSB&T Bldg., Wichita, Ks. 67202

Lease Name Mills "A" Well No. 1

Location NE SW Sec. 31 Twp. 30 Rge. 14 (E)    (W)    X

County Barber Total Depth 4664

Abandoned Oil Well X Gas Well X Input Well    SWD Well    D & A   

Other well as hereafter indicated   

Plugging Contractor Clarke Corp.

Address 107 W. Fowler, Medicine Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 1 Pm Day 8 Month 10 Year 1979

The above well was plugged as follows:

244' 8 5/8" casing w/265 sax cement. 4 1/2" casing set at 3952' w/100  
sax cement. Pref., at 3872' - Plug back to 3922' - Sand back to 3830' -  
Top sand w/4 sax mixed cement w/ dump bailer. Pull 2938' 4 1/2" casing.  
Build bridge at 240' & dump 5 yard's ready mix cement in 8 5/8" casing  
to top of casing. Harper Ready Mix - Harper Ks.

RECEIVED  
STATE CORPORATION COMMISSION

10-23-79

OCT 25 1979

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Wichita, Kansas  
Well Plugging Supervisor

INVOICED

DATE 10-24-79

INV. NO. 0747-W