

State of Kansas



UP2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 29 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Delaney of Leben Drlg. Inc. has this  
date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Leben-Bankoff

Complete Address: Brawer 2479 Tulsa, OK

Lease Name: Hughbanks Well No. A-1

Location: SW/NE/NE Sec. 27 Twp. 33s Rge. 9 (E)(W) W

County: Harper Total Depth 3780 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Delaney was instructed to plug the well as follows:

250 ft of 8 5/8 surface pipe cemented with 225 sacks. Fill

hole to 240 ft, plug, 1/2 sack hulls, 35 sacks cement. Mud

to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.

2 sacks cement in rat hole.

Very truly yours,

*D. Russell Bickerton*  
Conservation Division Agent