

State of Kansas



FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 4 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. D. M. Lester of Wood Oil Company has this date requested permission to plug the following described well:

Mr. Lester guarantees payment of the plugging fee.

Operator's full Name: Wood Oil Company

Complete Address: 800 Midstates Bldg., Tulsa, Oklahoma

Lease Name: Whaley Well No. # 1

Location: C NW NW Sec. 25 Twp. 33 Rge. 9 (E) (W) W

County Harper Total Depth 4605 Oil Well

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Lester was instructed to plug the well as follows:

251' of 8 5/8" surface pipe, cement circulated with 140 sacks.  
Fill hole with drilling mud to 250', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,  
*Archie Elving*