



16-077-20105-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Mark Hurst of H&H Casing Pulling has this date requested permission to plug the following described well:

Operator's Full Name: Leben Oil Corporation

Complete Address: Box 35528 Tulsa, Oklahoma 74135

Lease Name: Hughbanks Well No. 1

Location: NE NE SW Sec. 23 Twp. 33 Rge. 9W (E) (W)

County: _____ Total Depth: 4492'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereafter indicated: _____

Mr. Mark Hurst was instructed to plug the well as follows:

250' of 8 5/8" W/225 sx

4490' of 5 1/2 casing W/200 sx

Perfs 3725' Sand back to 3690' & dump 5 sx cement

Pumped 15 gel 8 hulls 10 gel, Released Plug & displaced

W/125 sx 50-50- pozmix 4% gel 3% cc

Allied Cementers Recovered 2700' of 5 1/2" csg. SIP 600#

Very truly yours,

M. Decker
Conservation Division Agent

STATE CORPORATION COMMISSION

APR 24 1981

CONSERVATION DIVISION
Wichita, Kansas