

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES, Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 21 1966
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Gale Metz of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Metz guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Loesch Well No. # 1

Location: C NW SW Sec. 16 Twp. 33 Rge. 9 (E) (W) W

County Harper Total Depth 4825' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Metz was instructed to plug the well as follows:

210' of 8 5/8" surface pipe, cement circulated with 180 sacks.
Fill hole with drilling mud to 200', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving