

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-077-20019-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed April 21, 1967.

Dear Sir:

Mr. Jack Gabbert of Gabbert-Jones, Inc. has this
date requested permission to plug the following described well:

Mr. Gabbert guarantees payment of the plugging fee.

Operator's full Name: Kimbark Exploration Ltd.

Complete Address: 201 University Blvd., Denver, Colorado 80206

Lease Name: Silcott Well No. # 2

Location: C SE SE Sec. 13 Twp. 33S Rge. 9 (E)(W) W

County Harper Total Depth 4521' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gabbert was instructed to plug the well as follows:

226' of 8 5/8" surface pipe, cemented with 150 sacks. Fill hole with
drilling mud to 225', 1st cementing plug, bridge with 1/2 sack of hulls,
and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd
cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks,
to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent