

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

OCT 14 1966

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Kimbark Exploration Company

Complete Address: 201 University Blvd., Denver, Colorado

Lease Name: Enderud Well No. # 1

Location: SE SW Sec. 14 Twp. 33 Rge. 9 (E)(W) W

County Harper Total Depth 4500' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

241' of 8 5/8" surface pipe, cement circulated. Fill hole with mud to 240', 10' rock bridge, and cement with 25 sacks, Fill hole with mud to 40', 10' rock bridge, and cement with 10 sacks to the base of the cellar.

Very truly yours,

Audie Cliving
 Conservation Division Agent