

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Berens of D.N.B. Drlg Inc has this

date requested permission to plug the following described well:

Mr. Berens guarantees payment of the plugging fee.Operator's full Name: Bankoff Oil CoComplete Address: Drawer 2479 Tulsa, OKLease Name: Babb Well No. 1Location: C SW/SW Sec. 13 Twp. 33S Rge. 9 (E)(W) WCounty: Harper Total Depth 4520 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Berens was instructed to plug the well as follows:200 ft 8 5/8 surface cemented with 150 sacks. Fill holeto 225 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud to40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.2 sacks cement in rat hole.

Very truly yours,

M. Russell B. Burtin
Conservation Division Agent