



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 27 1963  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Bob White of Empire Drilling Co. has this date requested permission to plug the following described well:

Mr. White guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Co.,

Complete Address: 650 4th National Bldg., Wichita, Kansas.

Lease Name: Babcock Well No. 1

Location: SE-SE Sec. 33 Twp. 15 Rge. 10 (E) (W) 26

County Gove Total Depth 4591 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. White was instructed to plug the well as follows:

197' 8 5/8" surface pipe cement circulated w/125 Sx.

Circulate hole with heavy mud, set plug @ 660' and 20 Sx cement.

" " 180' and 20 Sx cement  
with 1/4 sack hulls.  
" " 40' and 10 Sx cement  
with 1/2 sack hulls.

Very truly yours,

H. A. Nichols  
Conservation Division Agent