

State of Kansas



CPZ

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 8 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sweetman of Sweetman Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Sweetman guarantees payment of the plugging fee.

Operator's full Name: McCoy Petroleum Co. & Petroleum Inc.

Complete Address: 502 Union Center Wichita, Ks

Lease Name: Wharton Well No. 1

Location: NE/SE/SW Sec. 34 Twp. 33s Rge. 8 (E)(W) W

County: Harper Total Depth 4730 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Sweetman was instructed to plug the well as follows:

261 ft 8 5/8 surface pipe cemented with 200 sacks. Fill hole  
to 240 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud to 40 ft,  
plug, 1/2 sack hulls, 10 sacks cement to surface. 2 sacks  
cement in rat hole.

Very truly yours,

*A. Russell Wilkerson*  
Conservation Division Agent