

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

APR 8 1963

4-8-63

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Bill Walker of Rains & Williamson has this

date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains and Williamson Oil Co.

Complete Address: 412 Union Center Bldg., Wichita, Kansas

Lease Name: Lake Well No. # 1

Location: NW SE Sec. 14 Twp. 31 Rge. 14 (E) (W)

County Barber Total Depth 4605 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

88' of 13 3/8" sand string cemented with 50 sacks.

866' of 8 5/8" surface pipe cement circulated with 450 sacks.

Fill hole to 240' with mud, 1st cementing plug, 1/2 sack hulls,

cement with 20 sacks. Fill hole with mud to 40', 2nd cement-

ing plug, 1/4 sack hulls, cement with 10 sacks. Cement rat hole  
with 2 sacks.

Very truly yours,

Arthur Elving  
 Conservation Division Agent