

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1974
3-29-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lahar of B & B Drlg Inc has this

date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: National Oil Co

Complete Address: Suite 550 200 W Douglas Wichita, KS

Lease Name: Mills Well No. 1

Location: C SW/SE Sec. 5 Twp. 31s Rge. 14 (E)(W) W

County: Barber Total Depth 4540 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lahar was instructed to plug the well as follows:

Set 102 ft of 13" conductor string with 125 sacks cement.

Lost cir. at 450 ft. Set 782 ft 8 5/8 surface with 500

sacks cement. Pump plug, 25 sacks cement to 750 ft. 2nd

plug at 315 ft, 25 sacks cement. Mud to 40 ft, plug, 1/2

sacks hulls, 10 sacks cement to surface. 2 sacks cement

in rat hole. Pumped by Halliburton Cementing Co Great Bend,
Very truly yours, KS

J. Russell Binkerton
Conservation Division Agent