

KANSAS

Form CP-3  
Rev. 6-9-67

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202Intent to Drill,  
filed July 26, 1967.RECEIVED  
STATE CORPORATION COMMISSION

AUG 10 1967

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mack Oil Company

Complete Address 812 Union Center Bldg., Wichita, Kansas 67202

Lease Name Silcott Well No. # 1

Location C NE NE Sec. 17 Twp. 33 Rge. 9 (E) W

County Harper Total Depth 4830'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Mack Oil Company

Address 812 Union Center Bldg., Wichita, Ks. 67202 License No.       

Operation Completed: Hour 11:00 A.M. Day 9th Month August Year 1967

## The above well was plugged as follows:

250' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole was  
filled with drilling mud to 240', 1st cementing plug, bridged with 1 sack  
of Gel-Mud and 1/2 sack of hulls on fluid at 240', and cemented with 30 sacks,  
with cement from 230' to 140'. Hole was filled with drilling mud to 60',  
2nd cementing plug, bridged with 1 sack of Gel-Mud and 1/2 sack of hulls on  
fluid at 60', and cemented with 25 sacks, with cement 50' to the base of  
the cellar. Rat hole bridged and cemented with 5 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

8/10/67

INV. NO.

6114-W

Signed:

Audine Elving  
Well Plugging Supervisor