

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Loesch Well No. # 1

Location C ^{NW} NE SW MORCC Sec. 16 Twp. 33 Rge. 9 (E) (W) W

County Harper Total Depth 4825

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Rains & Williamson Oil Company

Address: 1425 Wichita Plaza Bldg., Wichita, Kansas License No.

Operation Completed: Hour 9:30PM Day 19th Month March Year 1966

The Above well was plugged as follows:

210' of 8 5/8" surface pipe, cement circulated with 180 sacks. Hole
was filled with drilling mud to 200', 1st cementing plug, bridged solid
with dry cement and hulls on fluid at 200', and cemented with 25 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with dry cement and hulls on fluid at 40', and cemented with 10
sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/21/66
INV. NO. 2912-u

Signed: Archie Elving
Well Plugging Supervisor