

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasIntent to Drill,
filed April 21, 1967.RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1967

CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Kimbark Exploration Ltd.Complete Address: 201 University Blvd., Denver, Colorado 80206Lease Name Silcott Well No. # 2Location C SE SE Sec. 14 Twp. 33S Rge. 9 (E) WCounty Harper Total Depth 4521'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Gabbert-Jones, Inc.Address: 830 Sutton Place, Wichita, Kansas License No. Operation Completed: Hour 2:00AM Day 7th Month June Year 1967

The Above well was plugged as follows:

226' of 8 5/8" surface pipe, cemented with 150 sacks. Hole was filled
with drilling mud to 225', 1st cementing plug, bridged with 2 sacks of
dry cement and 1/2 sack of hulls on fluid at 225', and cemented with 23
sacks. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40',
and cemented with 9 sacks to the base of the cellar. Rat hole bridged and
cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elving
Well Plugging SupervisorDATE 6/12/67INV. NO. 5365-W