

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 14 1966

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name Kimbark Exploration, LtdComplete Address: 201 University Blvd., Denver, ColoradoLease Name Enderud Well No. # 1Location SE SW Sec. 14 Twp. 33 Rge. 9 (E) (W)County Harper Total Depth 4500Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Knight Casing Pulling CompanyAddress: Box 405, Chase, Kansas License No. 436Operation Completed: Hour 12:15PM Day 8th Month Oct. Year 1966

The Above well was plugged as follows:

241' of 8 5/8" surface pipe, cement circulated. 4480' of 5 1/2" long string,
cemented with 100 sacks. This is an open hole. Bottom of the hole was
sanded to 4450', and cemented with 5 sacks, through the dump bailer.
3800' of 5 1/2" long string was recovered from the hole. Hole was filled
with mud to 240', rock bridge from 240' to 230', and cemented with 25
sacks. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/14/66INV. NO. 4096-uSigned: Audie Elving
Well Plugging Supervisor