

Form CP-3
Rev. 6-26-62

4
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued June 9, 1967.

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1967

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Kimbark Exploration Ltd.

Complete Address: 201 University Blvd., Denver, Colorado 80206

Lease Name Silcott Well No. # 1

Location C SW SE Sec. 14 Twp. 33 Rge. 9 (E) (W) W

County Harper Total Depth 4484'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 5:00PM Day 11th Month June Year 1967

The Above well was plugged as follows:

224' of 8 5/8" surface pipe, cemented with 150 sacks. 4478' of 5 1/2" long string,
cemented with 100 sacks. This is an open hole. Bottom of the hole was sanded
to 4450', and cemented with 5 sacks., through the dump bailer. 3511' of 5 1/2"
long string was recovered from the hole. Hole was filled with mud to 220',
rock bridge from 220' to 210', and cemented with 20 sacks. Hole was filled
with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to
the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/14/67
INV. NO. 5387-W