

40 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Empire Drilling Co.,

Complete Address: 650 4th National Building, Wichita, Kansas.

Lease Name Babcock Well No. 1

Location SE-SE Sec. 33 Twp. 15 Rge. 10 (E) (W) 26

County Gove Total Depth 4591

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 2:00P Day 24 Month 3 Year 1963

The Above well was plugged as follows:

197' - 8 5/8" surface pipe circulated w/125 Sx. cement.

Circulated hole with heavy mud, set plug @ 660' and displaced 20 Sx

cement thru DP. Heavy mud to 180' set plug with 1/4 sack hulls and dis-

placed 20 Sx cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 sacks cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR 27 1963

I hereby certify that the above well was plugged as herein stated. Wichita, Kansas

INVOICED
DATE 3/29/63
INV. NO. 6984-u

Signed: H. L. Nichols
Well Plugging Supervisor