

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 08 1978

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 077-20215-00-00 (of this well)

Operator's Full Name Energy Resources Group, Inc.

Complete Address 5015 N. Penn, Suite 100, Okla City, Okla - 73112

Lease Name J.C. Heath Well No. 1

Location 200' W of C - NW - NW - Sec. 6 Twp. 33^S Rge. 9 (E) (W) X

County Harper Total Depth 4344

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargents Casing Pulling Service

Address Box 506 Liberal, Kansas 67901 License No. 511

Operation Completed: Hour 2 pm Day 5 Month May Year 1978

The above well was plugged as follows:

261'-8 5/8" Casing w/ 600 sack Cement - 5 1/2" set @ 4344' w/ 200 sack
Cement - Plug off bottom w/ Cement - prof. 4480'-84' - Mix &
pump 20 sack Cement - 1 sack shells - 20 sack Cement to 3900' top
shut in w/ 300# press - Pull 5 1/2" casing to 240' mix & pump
5 sack gel - 50 sack Cement through 5 1/2" casing - pull pipe
to 35' pump 12 sack Cement to top of casing - Cap surface pipe
w/ weldon. Recased 3425' 5 1/2" casing
Pumped by Sargents Casing pulling

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 5-8-78
INV NO. 7262-W