

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 22 1975

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Robinson Oil Co

Complete Address 340 R.H. Garvey Bldg Wichita, KS

Lease Name Short B Well No. 1

Location E/2 SW/SW Sec. 35 Twp. 33 Rge. 8 (E) (W) W

County Harper Total Depth 4680

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Pipe Pullers Inc

Address Box 128 Ellinwood, KS License No. 462

Operation Completed: Hour 2:00 PM Day 20 Month 10 Year 1975

The above well was plugged as follows:

215 ft 8 5/8 surface cemented with 175 sacks. 4675 ft 4 1/2 long string  
cemented with 165 sacks. Top perf. 4442 ft. Sand to 4400 ft, 4 sacks  
cement with bailer. Pulled 3900 ft 4 1/2. Set 10 ft rock bridge at  
300 ft. Fill hole with 5 yds redmix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/23/75

INV. NO. 2097-W

Signed: [Signature]  
Well Plugging Supervisor