

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.  
Wichita, KS 67202

API Number 15-007 20, 351-0000

Operator's Full Name Lamberson Oil Co., Inc.

Complete Address Suite 1030, 200 West Douglas, Wichita

Lease Name McGrath Well No. 1

Location C NE 1/4 Sec. 9 Twp. 31 Rge. 14 (East) (West)

County Barber Total Depth 3110'

Abandoned Oil Well      Gas Well XX Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling

Address Chase, Kansas License No. 683

Operation Completed: Hour: 8<sup>00</sup> PM Day: 7 Month: 7 Year: 1981

Plugging Operations attended by Agent? All XX Part      None     

The above well was plugged as follows:

12 3/4" @ 108' w/150 sp  
8 5/8" @ 807' w/450 sp  
Set 4 1/2" @ 3089' w/75 sp  
Perfs - 2991 - 2999' Plug Back to 2955'  
Perfs - 2900' - 2910' Squeezed bottom  
w/35 sp. Dumped 12 gel 6 hulls 10 gel  
Released Plug & displaced w/175 sp 50/50 Reg  
4 7/8 gel 3 7/8 C.C. Cemented by Sun  
Recovered 2250' 4 1/2" Csg. SIP 250<sup>#</sup>

RECEIVED  
STATE CORPORATION COMMISSION  
7-15-81  
JUL 15 1981  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: M. V. Seiler  
Conservation Division Agent

**INVOICED**  
DATE 8-19-81  
INV. NO. 6165-W