

DISTRICT CONSERVATION AGENT'S REPORT

CRB

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION nw-sw-sw

SEC. 9 TWP. 31 RGE. 14-w

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Mills

Operator J.M. Huber Co. Inc. Address Box #460 Pratt-Kans.

Field _____ County Barber

Total Depth 4370 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 15 1/2 - 99 ft. Circulated with cement
10 3/4 - 782 ft. Circulated with cement -
5 1/2 casing set at 4360 ft. 200 sacks of cement
Plugged back to 4330 ft with rock - Pumped 5 sacks
of cement at 4330 ft - Shot off & pulled the 5 1/2 casing
and to 275 ft. Set rock bridge & 20 sacks of cement
at 275 ft. Mud to 35 ft - Plug & 10 sacks of
cement at the surface

RECEIVED
STATE CORPORATION COMMISSION
1-14-52
JAN 14 1952

CONSERVATION DIVISION District Conservation Agent
Wichita, Kansas

C. H. Stouck

Date 1-12-52

PLUGGING
FILE SEC 9 T 31 R 14 W
BOOK PAGE 137 LINE 31