

*Handwritten initials*

*Large handwritten 'R' or similar symbol*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 106-9

LOCATION NE-SW-NE

SEC. 9 TWP. 31 RGE. 14-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Boach

Operator J.M. Huber Corp. Address Box #460 - Pratt - Kans

Field \_\_\_\_\_ County Barber

Total Depth 4590 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 10 3/4 - 803 ft - Circulated with cement. 5 1/2 casing set at 4590 ft - Plugged back from bottom to 3180 ft - with mud - Taper Mills Plug & Chat. Mended 4 sacks of cement at 3180 ft - Shot off & Pelled the 5 1/2 casing - Filled with mud to 250 ft - Set Rock Bridge & 10 sacks of cement at 250 ft - Mud to 30 ft - Plug & 10 sacks of cement at the surface*

*Frank Carroll - Plugging Contractor*

Cons. Division

AUG 1 - 1949

8-1-49

*Wm. Stough*  
District Conservation Agent

Date KANSAS 7-29-49

**PLUGGING**  
FILE SEC-9-T31-R14W  
BOOK PAGE 106 LINE 9