

DISTRICT CONSERVATION AGENT'S REPORT

*R*  
*OPB*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION S.W.-S.E.-N.E

SEC. 9 TWP. 31 RGE. 14

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 2 Lease W.A. Roark

Operator J.M. Huber, Corp. Address Box #460 Pratt, Kans.

Field \_\_\_\_\_ County Barber

Total Depth 43.48 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 1 1/2" - 125 ft. Circulated with cement  
10 1/4" - 800 ft. Circulated with cement.  
2 1/2" casing set at 930 ft. Plugged back to 260 ft with  
mud & heavy Wells Plus. Filled with shot from 360 ft  
to 3580 ft. Dumped 5 sacks of cement at 3580 ft.  
Shot off. Pulled the 2 1/2" casing. Filled with mud to  
250 ft. Set Rock Bridge & 20 sacks of cement at 250 ft.  
Mud to 30 ft. Bridge & 10 sacks cement at the surface.

**PLUGGING**  
FILE SEC 9 T 31 R 14  
BOOK PAGE 147 LINE 26

APR 13 1950  
4-13-50

Q. R. Stough  
District Conservation Agent

Date 4-10-50