

DISTRICT CONSERVATION AGENT'S REPORT

CR

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 115-45

LOCATION CE/2 - SE-SW

SEC. 3 TWP. 31 RGE. 14-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease D.V. Nargis

Operator Standard Oil Gas Co Address Box #7 - Ellinwood - Kans-

Field _____ County Barber

Total Depth 4688 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 12 1/2 - 204 ft. Circulated with cement
8 1/2 set at 808 ft - Circulated with cement -
5 1/2 casing set at 4688 ft - Plugged back from bottom
to 3670 ft with Lane Well Plug - Cement to chat -
Mudbed 5 sacks of cement at 3670 ft - Shot & pulled
the 5 1/2 casing - Filled with mud to 2500 - Set Rock Bridge
& 20 sacks of cement at 2500 - Mud to 30 ft - Plug 10 sacks
of cement at the surface

Pipe Pulling, Inc.
Plugging Contractors

RECEIVED

District Conservation Agent

Date 10 - OCT 24 1949

STATE CORPORATION
COMMISSION
KANSAS
10-21-49

PLUGGING
FILE SEC 3 T 31 R 14W
BOOK PAGE 115 LINE 15