

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

RECEIVED
STATE CORPORATION COMMISSION
1-23-89
JAN 23 1989

API NUMBER 15-007-20,389-0000 (of this well) 6/89
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR KBW Oil & Gas Co. OPERATORS LICENSE NO. 5993

ADDRESS P.O. Box H Bethany OK 73008 PHONE # (405) 789-0178

LEASE (FARM) Lukens WELL NO. #1 WELL LOCATION NE-SW-NE COUNTY Barber

SEC. 28 TWP. 32 RGE. 11 (E) or (W) TOTAL DEPTH 4839 PLUG BACK TD unknown

(above 4000')

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 325' CEMENTED WITH 250 SACKS

CASING SIZE 4 1/2" SET AT 4503' CEMENTED WITH 250 SACKS

PERFORATED AT Approx. 3680' in Douglas Sand

CONDITION OF WELL: GOOD _____ POOR see back CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 50' of sand, 4 sx cement w/ dump bailer, pumped
3 sx hull, 10 sx gel, 50 sx cement, 10' sx gel, 1 sx hull, plug, 100 sx cement, 60-40 POZ,
2% C C, 2% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? None available IS ACO-1 FILED? No
Lee Brooks Oil Co., Inc. was operator (If not, explain) All information held tight. Lee Brooks
Oil Co., Inc. abandoned this well approx. 1983 without plugging.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1-23-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gorden Keen PHONE # (405) 787-0178

ADDRESS P.O. Box H Bethany OK 73008

PLUGGING CONTRACTOR Clarke Corp. LICENSE NO. 5105 6/89

ADDRESS Box 187 Medicine Lodge, Ks 67104 PHONE # (316) 886-5665

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Elmer J. Wogester
(Operator or Agent)

DATE: 1-18-89

①

Condition of well:

3/24/86 thru 4/3/86 - Perf, acidize, frac, test - no further info.

4/5/76 - hit tight spot - estimated at 3680'

4/6/76 - ran impression block - casing has collapsed, estimate perfs 3680', estimate collapse, tubing would not pass through tight spot.

State of Kansas



15-007-20389-0000

Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

APR 24 1989

EXPIRES

January 24, 1989

WELL PLUGGING NOTICE

Lukens #1
NE SW NE
Sec. 28-32S-11W
Barber County

KBW Oil & Gas Company
P. O. Box H
Bethany, OK 73008

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Handwritten signature of Shari Feist in cursive.

Shari Feist
Director
State Corporation Commission

DISTRICT #1 304 W. McArtor, Dodge City, KS 67801 (316) 225-6760