

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-077-20,890-000 (of this well) c/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR TXO Production Corp. OPERATORS LICENSE NO. 5171

ADDRESS 155 N. Market, Suite 1000, Wichita, KS. 67202 PHONE # (316) 269-7600

LEASE (FARM) Baringer WELL NO. 2 WELL LOCATION 1980' FEL COUNTY Harper
810' FNL &

SEC. 25 TWP. 32 RGE. 9 ~~XXXX~~ (W) TOTAL DEPTH 4050' PLUG BACK TD 3700'
4470' FSL

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 263' CEMENTED WITH 200 SACKS

CASING SIZE 4-1/2" SET AT 4045' CEMENTED WITH 225 SACKS

PERFORATED AT Stalnaker 3716-28'

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Pump plug & 25 sxs cement to 3600'.

Pull casing @ 2000'. Fill hole w/ mud to ± 300'. Dump 25 sxs cement. Fill hole w/ mud to 40', dump 10 sxs cement. Cut off surface casing.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? YES
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry W. Collins PHONE # (316) 886-5605

ADDRESS P.O. Box 125-B, R.R. #1, Medicine Lodge, KS. 67104

PLUGGING CONTRACTOR Clarke Oilfield Services LICENSE NO. 5105

ADDRESS 107 W. Fowler, Medicine Lodge, KS. 67104 PHONE # (316) 886-5665

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Cory West
(Operator or Agent)
Cory West

DATE: 8-25-87

RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1987
6/88
CONSERVATION DIVISION
Wichita, Kansas

2



Mike Hayden Governor
Keith R. Henley Chairman
Rich Kowalewski Commissioner
Margalee Wright Commissioner
Judith A. McConnell Executive Director

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

NOV 27 '87

EXPIRES

August 27, 1987

WELL PLUGGING NOTICE

Baringer #2
4470' FSL 1980' FEL
Sec. 25-32S-09W
Harper County

TXO Production Corporation
155 N. Market, Ste. 1000
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist
Director
State Corporation Commission