

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 007-22023-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Southwest Operating, Inc. OPERATORS LICENSE NO. 9697
ADDRESS c/o Cheyenne Oil Properties - Royalty Bldg. 315 N. 4th St. Suite 209 - 107 N. 4th St. Ponca City, OK 74601 PHONE # (405) 762-3479
LEASE (FARM) Nittler WELL NO. 14-1 WELL LOCATION CE/2 SE SE COUNTY Barber
SEC. 4 TWP. 31 RGE. 14W (E) or (W) TOTAL DEPTH 4643 PLUG BACK TD 4490

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____
SURFACE CASING SIZE 8 5/8 SET AT 870 CEMENTED WITH 400 SACKS
CASING SIZE 5 1/2 SET AT 4614 CEMENTED WITH 200 SACKS
PERFORATED AT 4380 - 4382

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Pump 20 sks cement to 4200' shot pipe and pulled to 870' and pumped 35 sks @ 870'. Pulled all pipe and filled hole with mud to 40'. Put 10 ks cement @ 40 - 0'.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon Approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: J.R. Sorrels PHONE # (405) 762-3479
Wichita, Kansas

ADDRESS 1128 N. 14th St. Ponca City, OK 74601

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547

ADDRESS P.O. Box 506, Liberal, KS 67905-0506 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Robert Sargent
(Operator or Agent)

DATE: Oct. 20, 1989

①

STATE CORPORATION COMMISSION
RECEIVED
OCT 23 1989
CONSERVATION DIVISION
Wichita, Kansas

9/86

6/90

15-007-22023-0000

MARINER RESOURCES
330 S. Main
Wichita, Kansas 67202
April 19, 1985

Southwest Operating, Inc. / Mariner Resources
10880 Wilshire Blvd., Suite 1205
Los Angeles, California 90024

RE: Southwest Operating, Inc. / Mariner Resources
#4-1 NITTLER
C E/2. SE/4, SE/4 4-315-14W
Barber County, Kansas

Sirs:

Submitted herewith is the geological report concerning the above captioned test. Data pertinent to the operation are tabulated below:

| | |
|------------------------------|----------------------------------|
| Spud: 3-20-85 | Rotary Complete: 3-30-85 |
| Contractor: Mohawk Drilling | Elevation: Laughlin-Simmons |
| Surface Pipe: 8 5/8" at 858' | Production Pipe: 5 1/2" at 4614' |
| Drill Time: 2300' to T.D. | Samples: 2500' to T.D. |
| DST: Western Testing (3) | Cores: None |
| Mud: Maverick | Log: Schlumberger (CNL-LDT, DIL) |

Geological formation tops as picked from samples and corrected to the open hole survey follow. All measurements are from the Kelly Bushing elevation.

Elevations: 1690' K.B.

1680' G.L.

| | | |
|--------------------|------|---------|
| Indian Cave Sand | 2765 | (-1075) |
| Stotler | 2931 | (-1241) |
| Emporia | 3041 | (-1351) |
| Heebner | 3626 | (-1936) |
| Lower Douglas Sand | 3777 | (-2087) |
| Lansing | 3818 | (-2128) |
| Stark | 4112 | (-2422) |
| Maquoketa (Viola) | 4368 | (-2678) |
| Simpson Shale | 4512 | (-2822) |
| Simpson Sand | 4531 | (-2841) |
| Arbuckle | 4612 | (-2922) |
| Total Depth | 4642 | |

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1985
10-23-85
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1985
9-16-85
CONSERVATION DIVISION
Wichita, Kansas

Drill stem
shut-in
rates

Well # 14



15-007-22023-0000

Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH MCCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

THIS NOTICE

JAN 23 1990

EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

October 23, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Southwest Operating, Inc.
City Plaza West, Suite 515-CP
5310 E. 3rd St. Cheyenne Oil Properties
Tulsa, OK 74135 Suite 209-Royalty Bldg.
107 N. 4th

Nittler 14-1
CE/2 SE SE
04-31-14W
Barber County

Gentlemen: Ponca City, OK 74601

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #1 304 W. McArtor

Dodge City, KS 67801

(316) 225-6760