

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-135-1904-0000 of this well) 6/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Pickrell Drilling Company, Inc. OPERATORS LICENSE NO. 5123
ADDRESS 110 N. Market, Suite 205, Wichita, KS 67202 PHONE # (316) 262-8427
LEASE (FARM) Humburg WELL NO. 2 WELL LOCATION SW SE COUNTY Ness
SEC. 25 TWP. 19S RGE. 22W or TOTAL DEPTH 4393' PLUG BACK TD 4393'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8 5/8" SET AT 252' CEMENTED WITH 160 SACKS
CASING SIZE 5 1/2" SET AT 4380' CEMENTED WITH 100 SACKS on btm plus
PERFORATED AT Open Hole 4380'-4385' 600 ft³ thru stage collar at 1500 ft.
CONDITION OF WELL: GOOD _____ POOR CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Mix & pump 300# cottonseed hulls in water. Pump 155 sx Allied ATL cement (605 ft³ = hole volume + 10 ft³). Mix 200# cottonseed hulls w/first cement. Recheck well for cement at surface after set-up time.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN December 9, 1987

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: Ed Mondero PHONE # (913) 798-2430
RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1987
12-2-87
CONSERVATION DIVISION
Wichita, Kansas

ADDRESS P. O. Box 375, Ness City, Kansas 67560

PLUGGING CONTRACTOR Allied Cementing LICENSE NO. N/A

ADDRESS Box 31, Russell, Kansas 67665 PHONE # (913) 434-8812

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack Curley
(Operator or Agent)

DATE: 12-1-87
Jack Curley - Engineer

①

State of Kansas



15-135-19014-0000

Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

MAR 02 '88

EXPIRES

December 2, 1987

WELL PLUGGING NOTICE

Humburg #2
SW SE
Sec. 25-19S-22W
Ness County

Pickrell Drilling Company, Inc.
110 N. Market, Ste. 205
Wichita, KS 67202


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,


Shari Feist
Director
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760