

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,185 - 0000 (of this well)

Operator's Full Name Thunderbird Drlg., et al

Complete Address Box 18407, Wichita, Kansas

Lease Name Schaben Well No. 1

Location C SW NW Sec. 24 Twp. 19 Rge. (E) (W) 22

County Ness Total Depth 4404'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 7 P Day 17 Month 4 Year 1976

The above well was plugged as follows:

RTD 4404' 8 4/8 csg set 422' cwc 250 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 600' thru drill pipe.

Heavy mud to 300' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1976
4-19-76
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red Massey
Well Plugging Supervisor

DATE 4-20-76

INV. NO. 3079-W