

15135-20399 0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company
Complete Address 705 4th Nat'l Bk. Bldg., Wichita, Kansas 67202
Lease Name Gillig "B" Well No. 2
Location C SE SW Sec. 24 Twp. 19 Rge. (E) (W) 22
County Ness Total Depth 4410
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Russ Casing Pulling
Address Box 1082 Great Bend, Kansas 67530 License No. 623
Operation Completed: Hour 11:15 A Day 23 Month 1 Year 1970

The above well was plugged as follows:

Total Depth 4410' 8 5/8 csg set at 277' cwc 200 sk.
5 1/2 csg set at 4398' cw 170 sk cmt.
Filled 5 1/2 csg W/sd (4350-4410) Dumped 5 sk cmt W/dump bailer. (4315-4350)
Cutoff and recovered 3300' of 5 1/2 csg.
Pumped thru 8 5/8 plug container with 20 sk gel W/3 sk hulls - 100 sk 50-50 poz 6% -
10 bbl water - release plug and pumped 20 sk 50-50 poz 6%.

I hereby certify that the above well was plugged as herein stated.

Signed: Lio F. Murray
Well Plugging Supervisor

INVOICED

DATE 1/25/71

INV. NO. 3249-W