

15 135-36740000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 27 1967
3-27-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Quality Oil Company

Complete Address: 6320 Jacqueline Wichita, Kansas

Lease Name Gillig "A" Well No. 2

Location C SE SE Sec. 23 Twp. 19 Rge. 22 (E) (W) X

County Ness Total Depth 4406

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knights Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 2 P Day 25 Month 3 Year 1967

The Above well was plugged as follows:

Total Depth 4406' 8 5/8 csg set at 402' cwc

4 1/2 csg set at 4396 cw 165 sc cement.

Filled with sand to 4380' and dumped 4 sc cement with dump bailer.

Recov. 2580' of 4 1/2 csg.

Set plug inside 8 5/8 csg at 400' Dumped 5 sc cement with dump bailer.

Filled to surface with 6 yds. readymix cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 3/27/67

INV. NO. 4951-W